



Description of Proposed Works

1. Provision of a three metre wide footpath/ cyclepath along the sections of the easement intended to carry the proposed route. The proposed route is shown in red on this drawing.
2. Bridge works to consist of the provision of all surface water runoff and collection in to existing channels, gullies and open drains, with drainage to existing drains and sewers/culverts.
3. Repairs to all structures including culverts and road R224 at Abbeyfeale, a footbridge over the Oolagh River at Portinard, and a footbridge over a farm road in Port Townland.
4. Fencing works to include the provision of timber post-and-rail fencing on the approaches to all bridges, on the approach roads, and also to high strengthening of stone walling sections.
5. Provision of signs and information boards at selected locations.
6. Provision of markings and signs at all level crossings including advance warning signs on the approach roads.
7. Provision of signs and information boards at selected locations.

NOTE:

A topographic cable has been included along the route of the trail in a conduit buried to variable depths and defined on plan by concrete marker approximately 100mm above the ground surface. The cable is contained within a surface mounted conduit. Location and depth of the cable to be established prior to any excavation works.

Notes:

1. All levels are in metres and relate to Ordnance Datum.
2. All dimensions are in millimetres - figure dimensions to be taken in preference to scaled dimensions.

Line	Code	Revision	Date	Drawn/Checked/Verified
0	6.8.12	Part 8 Planning		CH TH THCS

IMBERICK COUNTY COUNCIL
Comhille Chontle
 Lurimigh

MRG
 MRC Consulting Engineers Limited
 112, Main Street, Lurimigh, Co. Kerry
 Tel: 067 462012 Fax: 067 462013
 Email: info@mrgekerry.com

Project	Client	Project No.	Scale
GREAT SOUTHERN TRAIL	112053	112053	1:100